

PAVCOLATA

PAVIMENTAZIONE COLATA IN OPERA



Dimensions					
	Safety area	Impact area	Falling height HIC	Physical footprint	Number of users
	0 x 0 cm	mq	200 cm	0 x 0 x 0 cm	0

Characteristics

Age range

Fino a 12 anni

Materials



Made of UV stable EPDM rubber granules



Plan

Picture

Manufacturer

Pozza 1865 S.R.L.

Country of manufacturing

ITALY



Components list



PAVCOLATA - RUBBER FLOORING

MQ 1 Elastic anti-trauma draining paving for play area, composed of:

SUPPORTING LAYER (for HIC greater than 100 cm) cold casting of natural black rubber granules (recycled rubber) with controlled granulometry (6-9.5), bonded with polyurethane-based prepolymer, after application of polyurethane primer, all mixed with suitable machinery. **FINISHING LAYER** Application of polyurethane primer and subsequent formation of the wear layer created by casting agglomerate of coloured EPDM granules in paste form (monochromatic colour to be chosen from standard ones) with the addition of black rubber with a grain size of 1-4, bonded with polyurethane-based prepolymer spread with metal shims, special straighteners and smoothed. Surface thickness 'colour' 1. cm. Colours: melange 70 % EPDM / 30% SBR or according to customer request The rubber layer is applied on a 6/8 cm concrete slab with electro-welded mesh

METODO DI FISSAGGIO A TERRA DEI MONTANTI DEL GIOCO: Attrezzatura predisposta per fissaggio a terra mediante l'utilizzo di appositi telai metallici.

INFORMAZIONI RELATIVE ALL'ISPEZIONE: Ispezione visiva periodica - Controllo della pulizia dell'attrezzatura - Controllo degli interspazi tra terreno ed attrezzatura - Controllo della consistenza del terreno - Controllo delle fondamenta - Controllo degli spigoli - Controllo dell'eventuale mancanza di parti - Controllo dell'usura eccessiva delle parti mobili (snodi e boccole) - Controllo dell'integrità dell'intera attrezzatura. Per le aree gioco soggette ad uso intensivo o vandalismo può essere necessaria un'ispezione giornaliera. Ispezione annuale periodica: Potrebbe rendersi necessario lo smontaggio di alcune parti per la verifica